







Wall Legend		
External Brick Cavity Wall : 325mm o/a Inner Leaf: 100mm Stranlite aerated blockwork: 3.6N/mm ² min. 630kg/m ³ and thermal conductivity of 0.16W/mK Finished internally with 12.5mm plasterboard on dabs with joints taped and skimmed. Cavity: Fully filled with 125mm Knauf Dntherm 32 Ultimate insulation to achieve a 'U' value 0.20 W/m ² K [or similar approved] Outer leaf: Brickwork to LPA approval		325
Internal Load-bearing Wall : 100mm 100mm blockwork. Strength min. 7N/mm ² lightweight aggregate medium Density 1350-1600kg/m ³ . To be connected to external wall blockwork using strip ties at 225mm centers.		100
Internal Non-load bearing Wall : 70mm Metal Stud Stud partitions 100mm o/a/l, partitions finished with 15mm gypsum based plasterboard dry lining with taped joints min. 10 kg/m ² density.		70
All stud partitions between any room and a bedroom of a room containing a wc shall comply with the acoustic requirements of Approved Document 'E' section 5 internal wall type B: min. 40dB reduction with the use of sound insulation between studs.		40dB
Internal Load-bearing Timber Buttress Wall : 124mm o/a/l a.a.p. 70mm metal stud + 12mm ply both sides finished with 15mm gypsum based plasterboard dry lining with taped joints min. 10 kg/m ² density.		Buttress

Ventilation	
Natural ventilation with background ventilators and intermittent extract fans (guidance suitable only for less airtight dwellings) With a design air permeability higher than 5m ³ /(h.m ²) at 50Pa	
Minimum equivalent area of background ventilators for natural ventilation as Table 1.7 of AD Part F(1) 2021	
Habitable Rooms	- 8000mm ²
Kitchen	- 8000mm ²
Utility	- no minimum
Bathroom/ensuites	- 4000mm ²
WC	- no minimum
Please refer to window schedule for total required ventilation	
Notes: 1. The use of this table is not appropriate in any of the following situations and expert advice should be sought. • If the dwelling has only one exposed façade. • If the dwelling has at least 70% of its openings on the same façade. • If a kitchen has no windows or external façade through which a ventilator can be installed. 2. Where a kitchen and living room accommodation are not separate rooms (i.e. open plan), no fewer than three ventilators of the same equivalent area as for other habitable rooms should be provided within the open-plan space. 3. The total number of ventilators installed in a dwelling's habitable rooms and kitchens should be no fewer than five, except in one-bedroom properties, where there should be no fewer than four. 4. If a bathroom has no window or external façade through which a ventilator can be installed, the minimum equivalent area specified should be added to the ventilator sizes specified in other rooms.	
Minimum extract ventilation rates for intermittent extract systems	
Room	Intermittent extract rate
Kitchen	30 l/s [cooker hood to outside]
Utility	30 l/s
Bathroom	15 l/s
Ensuite	15 l/s
WC/Cloak	6 l/s



FIRST FLOOR PLAN

External Opening Schedule					
Ref:	location	structural opening	min trickle vent req.	lintel size	
W1 #	Bedroom 2	1800x1200mm	8000mm ²	2100	Part Q compliant. Fire egress window.
W2 ob	WC	600x1200mm	4000mm ²	900	Part Q compliant.
W3	Bed 1 Dressing	1800x1200mm	8000mm ²	2100	Part Q compliant
W4 ob	Bed 1 Ensuite	900x1050mm	4000mm ²	1200	Part Q compliant
W5 ob	Bed 1 Ensuite	900x1050mm	4000mm ²	1200	Part Q compliant
W6	Living	2400x1500mm	8000mm ²	2700	Part Q compliant
W7	Kitchen	900x1050mm	4000mm ²	1200	Part Q compliant
W8	Kitchen	900x1050mm	4000mm ²	1200	Part Q compliant
W9	Utility	600x1050mm		2100	Part Q compliant - share lintel with ED6
W10	Study	1200x1050mm	8000mm ²	1500	Part Q compliant
W11 ob	Bathroom	900x1050mm	4000mm ²	1200	Part Q compliant
W12 SG	Stair Hall	2700x2400mm		-	Window & Lintel by specialist
W13 #	Bedroom 4	1200x1200mm	8000mm ²	1500	Fire egress window.
W14 #	Bedroom 3	900x1200mm	8000mm ²	1200	Fire egress window.
RL01	Living	1500x2500mm		N/A	Rooflight lantern by specialist
RL02	Bathroom	550x780mm		N/A	Rooflight [Velux or similar approved]
RL03	Stair landing	550x780mm		N/A	Rooflight [Velux or similar approved]
RL04	Stair landing	550x780mm		N/A	Rooflight [Velux or similar approved]
RL05	Stair landing	550x780mm		N/A	Rooflight [Velux or similar approved]
RL06	Stair landing	550x780mm		N/A	Rooflight [Velux or similar approved]
ED1 SG	front entrance	2700x2100		3000	I.G. Ltd. 'Original' door type D04, or similar, with Stormguard 'Trimline Extra', or similar, low profile threshold. with side lights Part Q compliant.
ED2 SG	Bedroom 1	2700 x 2100		3000	UPVC bifold door set, with standard threshold. Toughened glazing. Part Q compliant.
ED3 SG	Lounge	3600 x 2100		3900	UPVC french door set with side lights, 900 doors, with standard threshold. Toughened glazing. Part Q compliant.
ED4 SG	Kitchen	4500 x 2100		4800	UPVC bifold door set, with standard threshold. Toughened glazing. Part Q compliant.
ED5 SG	Living	3600 x 2100		3900	UPVC bifold door set, with standard threshold. Toughened glazing. Part Q compliant.
ED6 SG	Utility	910 x 2100		2100	UPVC utility doorset with standard threshold. Toughened glazing. Part Q compliant. Share lintel with W09
# Egress hinges for escape SG Safety glass to windows & doors ob Obscure glazing					
ALL LINTELS TO HAVE A MINIMUM OF 150MM BEARING FOR LINTEL REFS REFER TO MANUFACTURERS SCHEDULE					
ALL FIRST FLOOR WINDOWS TO HAVE EASY CLEAN HINGES					
ESCAPE WINDOWS: THE WINDOW SHOULD HAVE AN UNOBSTRUCTED CLEAR OPENABLE AREA THAT IS AT LEAST 0.33M ² AND HAVE NO CLEAR DIMENSION LESS THAN 450MM HIGH AND 450MM WIDE (THE ROUTE THROUGH THE WINDOW MAY BE AT AN ANGLE RATHER THAN STRAIGHT THROUGH), APPROPRIATE ESCAPE CATCHES AND HINGES MUST BE FITTED TO ENSURE THIS CLEAR OPENING IS ACHIEVED.					

Internal Opening Schedule					
Ref:	location	door size	structural opening	lintel	
D1	Store	2 x 610 x 1981	1296 x 2025	N/A	
D2	Bedroom 1	838 x 1981	910 x 2025	N/A	
D3	Bed 1 Ensuite	838 x 1981	910 x 2025	N/A	
D4	W.C.	838 x 1981	910 x 2025	N/A	
D5	Bedroom 2	838 x 1981	910 x 2025	N/A	
D6	Bathroom	838 x 1981	910 x 2025	N/A	
D7	Study	838 x 1981	910 x 2025	N/A	
D8	Lounge	2 x 838 x 1981	1748 x 2025	Yes	
D9	Kitchen / dining	838 x 1981	910 x 2025	N/A	
D10	Utility	838 x 1981	910 x 2025	N/A	
D11	Bedroom 4	762 x 1981	838 x 2025	N/A	
D12	Bathroom	762 x 1981	838 x 2025	N/A	
D13	Bedroom 3	762 x 1981	838 x 2025	N/A	
L1	Elec meter			750mm	
M Denotes modified door					

GENERAL NOTES (External Window & Door Schedule)	
All external window and door schedules are to be read in conjunction with the construction specification	
For confirmation of door and window swings/handings, refer to relevant general arrangement floor plans and elevations.	
The External door & window openings indicated in this schedule are structural and sufficient tolerance must be allowed for the thickness of the cavity closer and building the window within the structure or post fixing the window	
For full details of lintels over openings, refer top Structural Engineers details & specification.	
Provide standard double glazed (BS EN 1279-1:2004) draught sealed PVCu windows manufactured to BS 7412	
Ground floor windows must be able to be securely half open to avoid summer over heating	
External doors to be solid PVC-U u-value 1.2w/m ² K All windows to be Triple Glazed Argon Filled, Low E Glass, PVC-U u-value 1.2w/m ² K	
Below 800mm measured from floor level for glazed screens and windows and 1500mm measured from floor level for doors and any side panels within 300mm of the door. Glazing in these areas shall be toughened safety glass to BS 6262: Part 4. Obscure glazing to Bathroom, WC and En-suite	

NOTES:

THE COPYRIGHT OF THIS DRAWING IS VESTED IN THE ARCHITECT AND MUST NOT BE COPIED OR REPRODUCED WITHOUT HIS WRITTEN CONSENT. DO NOT SCALE THIS DRAWING - USE FIGURED DIMENSIONS ONLY. ALL CONTRACTORS MUST VISIT THE SITE AND BE RESPONSIBLE FOR TAKING OR CHECKING ALL DIMENSIONS REQUIRED FOR THIS WORK.

REVISIONS

A 30.12.23 - Prelim Issue

House Type D [4B8P]
Open Market
AS - Plots 7,9,10
OPP - Plots 11

Total Internal Floor Area:
GIA = 300m² / 3229.1ft²
NIA = 298m² / 3207.6ft²



Twyford Lodge, Blayney's Lane
Greenhill, Evesham.
Worcs WR11 4TR

T : 01386 41898
M : 07979 965625
E : franco@adsvevesham.co.uk

www.adsvevesham.co.uk

PROJECT/CLIENT:

Proposed Development of Land
At 90 Winchcombe Road
Sedgeberrrow
Evesham, WR11 7UB
for: SHEILING HOMES

BUILDING REGULATIONS
House Type D

First Floor Plan

SCALE 1:50@A1 DATE 12 2023

DWG 21-16-HT D-02 A